

Knuc1特推/基盤S合同打ち合わせ --- 実験まとめ ---

佐久間, 理研

2024 8/5

<https://indico2.riken.jp/event/4942/>

News 1

PHYSICAL REVIEW C **110**, 014002 (2024)

Measurement of the mesonic decay branch of the $\bar{K}NN$ quasibound state

T. Yamaga,^{1,*} S. Ajimura,³ H. Asano,² G. Beer,^{4,†} H. Bhang,⁵ M. Bragadireanu,⁶ P. Buehler,⁷ L. Busso,^{8,9} M. Cargnelli,⁷ S. Choi,⁵ C. Curceanu,¹⁰ S. Enomoto,¹ H. Fujioka,¹⁶ Y. Fujiwara,¹³ T. Fukuda,¹⁴ C. Guaraldo,¹⁰ T. Hashimoto,^{2,15} R. S. Hayano,¹³ T. Hiraiwa,³ M. Iio,¹ M. Iliescu,¹⁰ K. Inoue,³ Y. Ishiguro,¹² T. Ishikawa,¹³ S. Ishimoto,¹ K. Itahashi,^{2,15} M. Iwai,¹ M. Iwasaki,^{2,‡} K. Kanno,¹³ K. Kato,¹² Y. Kato,² S. Kawasaki,¹¹ P. Kienle,^{17,†} H. Kou,¹⁶ Y. Ma,^{2,15} J. Marton,⁷ Y. Matsuda,¹⁸ Y. Mizoi,¹⁴ O. Morra,⁸ R. Murayama,² T. Nagae,¹² H. Noumi,^{3,1} H. Ohnishi,²³ S. Okada,²⁴ H. Outa,^{2,15} K. Piscicchia,^{25,10} Y. Sada,²³ A. Sakaguchi,¹¹ F. Sakuma,^{2,15,§} M. Sato,¹ A. Scordo,¹⁰ M. Sekimoto,¹ H. Shi,⁷ K. Shirotori,³ D. Sirghi,^{10,6} F. Sirghi,^{10,6} S. Suzuki,¹ T. Suzuki,¹³ K. Tanida,²¹ H. Tatsuno,²² M. Tokuda,¹⁶ D. Tomono,³ A. Toyoda,¹ K. Tsukada,¹⁹ O. Vazquez Doce,^{10,17} E. Widmann,⁷ T. Yamazaki,^{13,2} H. Yim,²⁰ Q. Zhang,² and J. Zmeskal⁷
(J-PARC E15 Collaboration)

<https://doi.org/10.1103/PhysRevC.110.014002>

News 2

- PAC(7/30-8/1)の結果 (unofficial)
 - E80はStage-2 approval
 - Beam line upgrade にも関わらずrecommendation
 - E73(2.5+13.5days)
- 1 月中旬からSXが既定路線
 - 年度内は E73(2.5+13.5days) E70comm.+productionの一部 E72の4時間 T98の1day E63 0.5 days
 - 2025夏前 E70 production


Original Schedule



特推

	2022				2023				2024				2025				2026			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Magnet	-		Purchase (S.C. wires)		Construction				Test & Commissioning				Physics Run				Analysis & Publication			
Polarimeter/NC	Design		Purchase & Assembly				Test & Commissioning													
CDC	Design				Construction				Test & Commissioning											
Fiber tracker	Design								Construct.		Test & Commis.									

基盤S



Experiments@K1.8BR

- **Present CDS** ~ within FY2024
 - ✓ E73 (${}^3\Lambda$ H lifetime) 25d@80kW





need 9 months

- **Hyp-TPC** ~ before summer of FY2025
 - ✓ E72 (Λ^*) 14d@80kW



need 1 year





- **New CDS with K1.8BR modification**
 - ✓ E80 ($K^-ppn \rightarrow \Lambda d/\Lambda pn$) ~14+21d@90kW
 - ✓ P89 ($J^P(K^-pp)$) 56d@90kW
 - ✓ E57 (K^-d atm) 7d@80kW \rightarrow ~30d@80kW




Current Schedule

now ↓

	FY2022				FY2023				FY2024				FY2025				FY2026				FY2027			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
SC Solenoid Magnet	Design		Purchase (SC Wire)		Construction				Stored at KEK				Installation	Integration, Test & Commissioning		Commissioning w/ Beam		Physics Run		Analysis & Publication				
CDC	Design				Construction				Test & Commissioning															
NC	Design & R&D								Purchase (Scinti.)		Assembly		Test & Commissioning		E80 Experiment									
K1.8BR Beam Line	E73(CDS) → E72(HypTPC) Experiments												Upgrade											





Budget Situation

We have already secured the budget to construct the CDS.

- The magnet and CDC cost have been covered by **“Grant-In-Aid for Specially Promoted Research by JSPS (FY2022-26)”**.

Superconducting solenoid magnet	~370M JPY
CDC (cylindrical drift chamber)	~54M JPY



- The CNC will be built with a new budget, **“Grant-in-Aid for Scientific Research (S) by JSPS (FY2024-28)”**.

CNC (cylindrical neutron counter)	~80M JPY
-----------------------------------	----------



Systematic investigation of the light kaonic nuclei


- Systematic measurement will be promoted
 - Mass number dependence
 - Binding energy, Branching ratio, q dependence, ..
 - Spin/parity determination
- Extract internal structure with theoretical investigations

✓ Solid angle: x1.6
 ✓ Neutron eff.: x7



	Reaction	Decays
$\bar{K}N$	$d(K^-, n)$	$\pi^{\pm 0} \Sigma^{\mp 0}$
$\bar{K}NN$	${}^3\text{He}(K^-, N)$	$\Lambda p / \Lambda n$
$\bar{K}NNN$	${}^4\text{He}(K^-, N)$	$\Lambda d / \Lambda pn$ E80 ← first step
$\bar{K}NNNN$	${}^6\text{Li}(K^-, d)$	$\Lambda t / \Lambda dn$
$\bar{K}NNNNN$	${}^6\text{Li}(K^-, N)$	$\Lambda \alpha / \Lambda dd / \Lambda dpn$
$\bar{K}NNNNNN$	${}^7\text{Li}(K^-, N)$	$\Lambda \alpha n / \Lambda ddn$
$\bar{K}\bar{K}NN$	$\bar{p} + {}^3\text{He}$	$\Lambda\Lambda$





a first step of the systematic investigation

$\bar{K}NNN$ @ E80

via ${}^4\text{He}(1 \text{ GeV}/c \text{ } K^-, n)$ reaction

① Establish the existence of $\bar{K}NNN$




➤ “K-ppn” \rightarrow Λd 2-body decay

② Study the multi-particle decay mode of $\bar{K}NNN$ toward understanding its internal structure

➤ “K-ppn” \rightarrow Λpn 3-body decay

● Feasibility study of spin-spin correlation measurement for P89 (J^P determination of $\bar{K}NN$)



➤ e.g., installing a prototype module of a polarimeter tracker



the sign of the “K-ppn”


Beam intensity	90kW
Beam time	1+1+3 weeks

New Cylindrical Detector System (CDS)



- ✓ **Solid angle:** **x1.6** (59% → 93%)
- ✓ **Neutron eff.:** **x7** (3% → 12%x1.6)

New CDS



Superconducting Solenoid Magnet

- Same design as “the detector solenoid magnet” for COMET-I

being constructed in cooperation with the J-PARC Cryogenics Section

- 3.3m x 3.3m x 3.9m, ~108t in total
- Max. field of 1.0T @ center
 - 189A – 10V
- NbTi/Cu SC wire, 98km in total
- **Conduction-cooling with GM*3**
- Semi-active quench-back system
- **Will be completed in FY2024**




Will be completed in FY2024

SHI FA-50 (air cooling) 13 RDE-418D4



Completed in FY2023




Completed in FY2023




Completed in FY2022

Schedule of Superconducting Solenoid Magnet






Cylindrical Drift Chamber (CDC)


- 3 times the length of the existing CDC
 - Gas: Ar/CO₂=90/10
- The same design of the present end-cap
- Readout systems are reused



Completed this month, and commissioning will soon start @ J-PARC



Signal board




ASD preamplifier board



Cylindrical Neutron Counter (CNC)

- scintillator array: 2 layers, 12cm thickness
- Neutron detection efficiency of 12~36%
- 56+80=136 modules
 - ELJEN EJ-200: (T)60mm, (W)60mm, (L)3,000mm
- 1.5-inch FM-PMT [H8409(R7761)]
& MPPC array [S13361-6050AE-04]
- **Will be completed in FY2025**



We have achieved 60-70 ps (preliminary)

2,600mm



Prototype @ K1.8BR, June

136 scintillators in total

- 56 segments @ r548~608mm
 - 112 FM-PMTs
- 80 segments @ r780~840mm
 - 160 MPPC-arrays

Support Structure

- CNC is supported at upstream, downstream and middle position
 1. pillars are mounted on the inner cylinder of the magnet
 2. ring structures are installed on the pillars
 3. each module is mounted on the ring structures
- CDC is installed by inserting a long frame bar into the center of the CDC and magnet




Will be prepared in FY2025-26

CDC Installation

- CDC is installed by inserting a long frame bar into the center of the CDC and magnet
 - We plan to use a splittable bar twice the length of the solenoid.

Will be prepared in FY2025-26

- Service space equivalent to the installation area of the magnet is required downstream of the magnet
 - to prepare and install the CDC by rolling it in and out of the magnet



K1.8BR Upgrade


- We have proposed a new configuration of the beam line

Shorten the beamline ($\sim 3.7\text{m}$) by removing the final D5 magnet

➤ **1.0 GeV/c K^- intensity increases 1.6 times**

with $\pi/K \sim 2$

Relative beam-line length (beam yield)	D4+D5	D4
Present CDS	0 (x1)	-3.7m (x1.6)
New CDS	+1.2m (x0.9)	-2.5m (x1.4)



K1.8BR Upgrade

- We have consulted with the HD-G and the Radiation Control Section

➤ radiation application is required





- Process

1. Removal of D5/detectors/cables/etc.
2. Installation of new solenoid
3. Re-arrangement of shield
4. Re-installation of cables/PPS/etc.

It will take ~6 months

- **We would like to upgrade K1.8BR in late FY2025 – early FY2026**

➤ the application should be submitted in early FY2025



possible to rearrange the shields without purchasing new ones

Estimated Cost of the K1.8BR Modification

Item	Cost (k JPY)
Cable removal	3,000
Shield reconfiguration	7,000
D5 removal	1,000
PPS and other interlocks rearrangement	5,000
total	16,000

We are now trying to reduce costs further.

議論のネタ

- 山縣さんE62のペーパー
- K+(中須賀・慈道)
- 慈道計算、サイズ？
- 緒方さん（九大）と議論